

Bill of Quantity

ESTIMATE OF WORK (G/N,F/S,E,G/S Wards)						
(PART B) Mechanical Desludging						
Planning, Designing and Construction of RCC community toilet blocks under Lot 12 contract.						
Sr.No.	Item No.	Description	Qty	Rate	Per	Amount
1	R3-SBM-12-9	Mechanical De-sludging Of septic tank of any size with a dredging pump of capacity at least 1 HP. Dredging pump erected on winch, lowered with chain pulley fitted of the movable winch. Collection of pumped out sludge in a suction vehicle with a truck mounted water tank of 6000 liters capacity or any other mechanical means. the rate includes labours drivers, the fuel cost to operate the DG set, fuel for suction vehicle (transport and operation), and transportation of the removed sludge (Liquid and solid) for any distance. All the taxes inclusive.	432	2491	Seat	1076112
		Estimated Cost				1076112